



The SMARTENERGY six-pack series
 Online advanced training & B2B on game changing energy trends
 4 topics - 6 online sessions each

Hydrogen Energy communities Smart grids Smart buildings

Use of Solid Oxide Fuel Cell for clean energy production from biogas

Prof. Massimo Santarelli, PhD
Department of Energy, Politecnico di Torino (IT)

March 17th, 2021

DEMOSOFC
 FCH2-JU PROJECT



POLITECNICO DI TORINO



Imperial College London

H2020 Fuel Cells and Hydrogen 2 Joint Undertaking under Grant Agreement No. 671470 Demonstration of large SOFC systems fed with biogas from WWTP



+



=



WASTE WATER

SOFC

ENERGY

SOFC:

Highest efficiency in energy recovery from biogas 50-56%

Industrial size SOFC plant in Europe (110 kW_e + 55 kW_{th}) fed by biogas from sewage sludge





POLITECNICO DI TORINO



Imperial College London ₂

Plant layout





Gas holder

Sludge HEX room

Biogas

Electrical

HRU water

Cmp air

Electrical connection

Grid interface



Buildings works done at the SMAT site


DEMOSOFC site before the project start



Concrete basement




Piperack




Technical buildings



Issue: Biogas purification



	H ₂ S (ppm)	Si (mgSi/m ³)	CH ₄ (%)
Average	28.66	3.78	63.57
Min	0.00	0.00	56.04
Max	71.05	9.43	70.35




• H₂S
• Si


Contaminants

Biogas purification system: lead & lag configuration


Required purification level for SOFC
H₂S: 30 ppb
Siloxanes: 10 ppb



NOMINAL OPERATION




ISLAND MODE




Thermal recovery system and activities


- **Exhaust gases** are found at around **200-250°C** and are cooled down by controlling the water side (dew point is ~ 36 °C at full power but condensation should be avoided)
- **Thermal recovery on SOFC side** is performed by using a mixture of water-glycol (30% glycol) with set-point temperatures of **45°C (inlet) and 70°C (outlet)**. Water flow rate is adjusted by using a dedicated PID controller.
- A mixing valve, controlled by another PID, is used to guarantee 45°C at the HEX inlet and avoid condensation.
- On the **sludge side**, sludge is heated up from ~ ambient temperature **to 40°C** (a PID controller is available to regulate the flow rate in order to guarantee a fixed outlet temperature)




Thermal recovery system and activities



Primary pumps, valves and hydraulic separator



Secondary pumps with flow meters






Secondary double pipe HEX, expansion tank






Sludge pump and flow meter

Biogas clean-up


H₂S concentration - Clean-up unit




Siloxanes concentration - Clean-up unit




H₂S: 52.62 mg/m³
Siloxanes: 4.20 mg_{Si}/m³



Ads. capacity 85 (mgS/gAC)




Ads. capacity 150 (mgD4/gAC)




H₂S: 0 mg/m³
Siloxanes: <0.1 mg_{Si}/m³


SOFC Electrical Power production – Module 1



SOFC efficiency – Module 1



SOFC electrical efficiency vs %CH₄




Some results: emissions



Species	Unit	Measured value
H ₂ O	Vol-%	4.7
CO ₂	Vol-%	3.4
CO	mg/m ³	<9
CH ₄	mg/m ³	<2
N ₂ O	mg/m ³	<8
NO	mg/m ³	<20
NO _x (as NO ₂)	mg/m ³	<20
SO ₂	mg/m ³	<8
C ₂ H ₆	mg/m ³	<14
HCHO	mg/m ³	<7
HF	mg/m ³	<10
HCl	mg/m ³	<10
SO ₂	mg/m ³	<10
O ₂	Vol-%	18.3
Particulate	mg/m ³	0.01

Particulate emission during steady state



Exhausts from biogas-fed SOFC are cleaner than the surrounding air

Plant optimization analysis:




- Moving from underground pipeline to external (covered) pipeline
- Removal of twin pumps
- Reduction of UPS size
- Simplification of the technical building (→ containerized solution)
- Optimization of the cleaning system

	Actual Cost [€]	Estimated Cost [€]	Reduction
Mechanical Works	174.562	65.502	-63%
Electrical Works	173.913	100.819	-42%
Civil Works	191.920	23758	-88%
Clean-up system	221.087	132.652	-40%
Auxiliary works	91.677	54.597	-40%
TOTAL	853.159	377.328	-56%



**Future perspectives
for SOFC in the
WWTP sector
and some economic
considerations**

SOFC energy coverage and cost savings in the WWTP






Savings per year so far:


EL 59'633 €/yr

TH 17'004 €/yr


TOT 76'637 €/yr




Which should be the price of an SOFC system in a WWTP?



Power output (kW)	100	250	500	1000
Cost of electricity (€/kWh)	0.123 €	0.102 €	0.099 €	0.094 €






SOFC-CHP system investment cost to have the same Cost of Electricity of the ICE case study



Potential markets analysis

- Minimum entering load for WWTP with anaerobic digestion: 20'000 P.E. (20'000 P.E. ~ 40 kW SOFC)
- Biogas specific production: 10-29 l/P.E./day (value for conservative calculation: 10 l biogas/P.E./day)
- Methane content: 60%
- Capacity factor: 95%
- SOFC electrical efficiency: 53%

UWWTD treatment plants




Potential biogas production in EU
1.86 - 5.44 billion m³/y



Potential SOFC installations in EU
930 - 2550 MW_{el}

XS	20-60 kP.E.	25 – 80 kW
S	60-150 kP.E.	80 – 200 kW
M	150-350 kP.E.	200 – 500 kW
L	350-750 kP.E.	500 - 1000 kW
XL	>750 kP.E.	1000 - 1500 kW





Thank you!

Prof. Massimo Santarelli, PhD

Department of Energy, Politenico di Torino (IT)

DEMOSOFC has an overall budget of 5.9 million of euro and is receiving 4.2 million euro funding from the Fuel Cells and Hydrogen 2 Joint Undertaking under grant agreement No 671470. This Joint Undertaking receives support from the European Union's Horizon 2020 research and innovation programme, Hydrogen Europe and Hydrogen Europe research. The project is coordinated by the Energy Department of Politecnico di Torino (IT). The partners are: SMAT (IT), Convion Oy (FI), VTT Research Center (FI), Imperial College of Science Technology and Medicine (UK).



demosofc@polito.it



www.demosofc.eu



DEMOSOFC Page



Steps POLITO



Steps POLITO



POLITECNICO DI TORINO



Imperial College London



**BACK UP
SLIDES**

Buildings works done at the SMAT site

- Construction of a concrete basement with underground piping to host the cleaning system and the SOFC modules

Underground biogas pipes duct are separated from others for safety reasons

DEMOSOFC site before the project start



Concrete basement



Buildings works done at the SMAT site

- Construction of a 100+ meters biogas pipeline to transfer biogas from the gas holder area to the DEMOSOFC area, and exchange water for heat recovery, compressed air and electrical connections.

Piperack






Buildings works done at the SMAT site

- Construction of a dedicated building with 3 dedicated rooms for:
 - Electrical cabinets
 - Heat recovery pumps and collectors
 - Control room
- Construction of other side-buildings for auxiliary gases and UPS.

Technical buildings





Biogas production historical trend



Number of modules	1	2	3	4
Biogas share for electricity production	26.7%	53.4%	76.5%	97.8%
Equivalent capacity factor at full load	100.0%	99.8%	95.7%	87.3%
Number of forced shut-downs per year	0	0	1	4
Average electrical efficiency	53.16%	53.15%	53.05%	52.66%
Average thermal efficiency	80.00%	79.96%	79.09%	77.35%

OVER A TOTAL PRODUCTION OF AROUND 110 kW



The total auxiliary consumption (including all the biogas treatment section, heat recovery, electrical and control parts, conditioning of the technical building, etc.) is around 11.72 kW.


The value is dominated by the biogas treatment section (two chillers, blower, compressor) and all the equipment within the container (especially ventilation and cooling during Summer). The two sections together account for 77% of the consumption.

Capacity factor and stops of the plant


	Hours ON - h	Electrical Energy - kWh	Capacity factor - %
Tot. SOFC1	6,537	283,376	46.64%
Tot. SOFC2	7,710	320,115	67.70%
Tot. DEMOSOFC	14,247	603,492	55.00%

→ OFF periods were due to:


- Cleaning system → freezing problem at the beginning (then solved), planned (every 6'000 hours) and unplanned maintenance on the biogas compressor and blower.
- SOFC → air pre-heater maintenance, island mode testing and checking, maintenance on stack module 1.
- Control system → in the first 6-8 months the software was finalized and updated based on the experience gained onsite.
- Authorization → time required to renew the authorization and install the power meter requested



Electrical works




Mechanical works



Actual Cost [€]

Mechanical Works	174.562
Electrical Works	173.913
Civil Works	191.920
Clean-up system	221.087
Auxiliary works	91.677
TOTAL	853.159

Civil works



Auxiliary works

